CHITALDRUG DIVISION.

Notice dated 31st October 1928.

Notice is hereby given that the sealed tenders will be received at the Office of the Executive Engineer, Chitaldrug Division, up to 4th December 1928, for constructing Mutton Stalls at Davangere, Chitaldrug District. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of November 1929.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Chitaldrug between the hours of 11 A.M. to 5 P.M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed :—

Description of work	Unit of work	Rate per unit

4. Each tender must be accompanied by a deposit of Rs. 500 in cash or Government Promissory Notes, as earnest money and be superscribed "Tender for constructing Mutton Stalls at Davangere Town," in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Superintending Engineer, Shimoga Circle, Shimoga, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond ; in default of which, his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the Notice Board in the Executive Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

Abstract showing the list of quantities for constructing Mutton Stalls at Davangere Town, Chitaldrug District.

No.	Items of work	Per	Quantity
1	Earthwork excavation of foundation and filling in the basement with available earth.	C.yd.	133
2	Earthwork filling in basement with consolidation and carting of earth.	,,	35
3	Burnt stone jelly concrete in chunam	C.ft.	1,112
4	Burnt stone slabs 6" thick	S.ft.	302
5	Trap stone in mud	C.ft.	1,858
6	Burnt brick in mud	,,	310
7	Burnt brick in mud superstructure	,,	8,941
8	M. S. M. Railway Rail 40 lbs. per foot old with fish plate, bolts, nuts, etc., complete.	R.ft.	422
9	Teakwood work wrought and put up	C.ft.	159·11
10	Teakwood windows with battened shutters $\frac{3}{4}$" dia. iron bars, iron fittings, iron clamps, etc., complete, as per marryats specification.	S.ft.	96
11	Teakwood battened doors including iron clamps, iron fittings, etc., complete as per marryats specification.	,,	46
12	Roofing with First Class Mangalore tiles on teak reepers 2"×1" the eave tiles should be renewed down to the rafters with a teak batten 2"×1".	Sqr.	38·64
13	Teakwood eave board ornamental 9" wide $\frac{1}{2}$" thick including painting.	R.ft.	199
14	Burnt brick in mortar cornice 12"×9" including plastering	,,	345
15	Burnt brick in chunam coping 9" over wall including plastering.	,,	22
16	Burnt brick in chunam parapet wall ornamental over front wall including plastering as per design.	,,	55

No.	Items of work	Per	Quantity
17	Burnt brick in chunam parapet wall ordinary 2 feet high including plastering and moulding at top.	R.ft.	59
18	Flat terrace	Sqr.	3·02
19	Flooring with burnt stone slabs on 3" concrete including cement pointing.	"	31·30
20	Chunam plastering	"	129·96
21	Pillasters	Each	5
22	Preparing and fixing iron gate as per design	"	1
23	Constructing U shaped drain in surki concrete in stone jelly and cement plastering.	L. S.	...
24	Providing iron chains and hooks for hanging mutton, 2 for each stall.	Each	56
25	Ornamental work around windows and gate	"	8
26	White and colour washing	Sqr.	129·96
27	Repairing the existing well	L. S.	...
28	Preparing sham windows in front wall	"	...
29	Providing and fixing 1 foot curb stone between stalls ...	R.ft.	162
30	Burnt stone slab pillars 6" thick, 1 foot width roughly dressed, cutting groves for resting bressumer.	S.ft.	220
31	Burnt brick in chunam arch work as per deduction in superstructure.	C.ft.	90
32	Parapet wall above roof of stalls outside alround including plastering.	R.ft.	288
33	Burnt brick in chunam cornice 9"×9" including plastering	"	63

Abstract Notification dated 13th October 1928.

The attention of the public is hereby invited to the advertisement pages 1149 and 1150, Part VI of the *Mysore Gazette* of 18th October 1928, calling for tenders for the work of constructing an additional block to the Travellers' Bungalow at Chitaldrug.

Abstract Notification.

The attention of the public is hereby invited to the advertisement page 1185 of the *Mysore Gazette* of Part VI, 1st November 1928, calling for tenders for the work of constructing Town Police Station at Davangere in Davangere Taluk.

Abstract Notification.

The attention of the public is hereby invited to the advertisement page Nos. 1183 to 1184 of the *Mysore Gazette* of Part VI, 1st November 1928, calling for tenders for the work of Improving Bhattarahally Tank Feeder Channel in Molkalmuru Taluk.

A. TANDONI RAO,
Executive Engineer.

KOLAR DIVISION.

Abstract Notification, dated 11th October 1928.

The attention of the public is hereby invited to the advertisement page No. 1148 and 1149, of the *Mysore Gazette*, dated 18th October 1928, calling for tenders for the work of Restoring Munigamadu Anicut below Byrasagara Tank, Chikballapur Taluk. Last date of tender is 12th November 1928.

N. LAKSHMINARASIMHAIYA,
Executive Engineer.